

UNCLASSIFIED

AD NUMBER

ADB023860

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 12 AUG 1977. Other requests shall be referred to Electronic Systems Div., Hanscom AFB, MA 01731.

AUTHORITY

USAFGL ltr 7 Sep 1982

THIS PAGE IS UNCLASSIFIED

UNCLASSIFIED

AD B023860

AUTHORITY: USAFGL  
1tr, 7 Sep 82



UNCLASSIFIED

18 17  
ESD-TR-77-310 ✓



2 14  
Report No. 131500-613 ✓  
12 August 1977

AD B 023860

11 12 Aug 77

6  
WIND TEST REPORT  
FOR THE  
AN/TRN-41 TACAN NAVIGATIONAL SET

12 10p.

Distribution limited to U. S. Government agencies only;  
Reason: Test and Evaluation. 12 August 1977. Other  
requests for this document must be referred to  
Department of the Air Force, Headquarters Electronic  
Systems Division (AFSC), Hanscom Air Force Base,  
Massachusetts 01731, Attention: PPG.

Prepared for:  
Department of the Air Force  
Headquarters Electronic Systems Division (AFSC)  
Hanscom Air Force Base  
Massachusetts 01731

DDC  
NOV 3 1977  
REGISTERED  
F

Prepared by:  
E-Systems, Inc., Montek Division  
2268 South 3270 West  
Salt Lake City, Utah 84119

15  
Contract No. F19628-75-C-0200  
CDRL Item A00Y

AD No. \_\_\_\_\_  
DDC FILE COPY

408354

15

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER <b>ESD-TR-77-310</b>	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle)  <b>WIND TEST REPORT FOR THE AN/TRN-41 TACAN NAVIGATIONAL SET</b>		5. TYPE OF REPORT & PERIOD COVERED
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s)  <b>None</b>		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS <b>E-Systems, Inc., Montek Division 2268 South 3270 West Salt Lake City, Utah, 84119</b>		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS <b>Electronics Systems Division (AFSC) Hanscom AFB Ma. 01731</b>		12. REPORT DATE <b>12 August 1977</b>
		13. NUMBER OF PAGES
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report)  <b>Unclassified</b>
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE <b>N/A</b>
16. DISTRIBUTION STATEMENT (of this Report)		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)  <b>Distribution limited to U.S. Government agencies only; Reason: Test and Evaluation. 12 August 1977. Other requests for this document must be referred to Department of the Air Force, Hq ESD (AFSC), Hanscom Air FORCE Base Ma. 01731, Attention: DRI</b>		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  <b>AN/TRN-41 TACAN NAVIGATIONAL SET</b>		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  <b>Wind Test Report for the Navigational Set, TACAN, AN/TRN-41.</b>		

**WIND TEST REPORT**  
**for the**  
**NAVIGATIONAL SET, TACAN, AN/TRN-41**

This report describes the wind test as defined in the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41, 131500-415.

1. **Test Identification.** Wind test as defined in Appendix IV-J (wind test procedure) of the Equipment Test Plan for Navigational Set, TACAN, AN/TRN-41.
2. **Functional Purpose of Test.** This test forms a part of the AN/TRN-41 system qualification tests.
3. **Test Objectives.** To demonstrate that the AN/TRN-41 will meet the wind requirements of paragraphs 3.2.5.1.9 and 4.2.1.4.3.10 of Specification No. 404L-701-5017A, Part 1 of 2 parts (20 August 1976).
4. **Description of Test Article.** The AN/TRN-41 system consisting of the following was used for the tests:

Receiver-Transmitter	RT-1202/T
Antenna	AS-3132/T
Antenna Support	AB-1237/T
Filter, DC Power	F-1439/T
Interconnecting Cables	
5. **Summary of Test Results.** The AN/TRN-41 showed no functional or physical degradation during the wind test.
6. **Description of Test Facilities and Procedures.** The test facilities and test procedures are described in Appendix IV-J of the Equipment Test Plan.
7. **Test Setup Diagrams.** The test setup diagrams are provided in Appendix IV-J of the Equipment Test Plan.

**12. Certification.** The data sheets shown in Attachment 2 have been signed by a Montek Quality Assurance representative and a DCAS representative, certifying that the test results are authentic, accurate, current and in accordance with the related test plan.

[illegible]

**ATTACHMENT 1**

**TEST EQUIPMENT**

# TEST EQUIPMENT

<u>Description/Manufacturer</u>	<u>Model</u>	<u>Calibration Due Date</u>
Oscilloscope, Tektronix	465	7/6/77
Signal Generator, RF, H.P	612A	6/23/77
Peak Power Meter, Boonton S/N B-463	8900B	9/19/77
Pulse Generator, Data Pulse	110B	5/12/77
Counter, Fluke	1953	8/12/77
Half-Ampl. Det. Montek	131500-702	N/A
RF Detector, Montek	135203-100	N/A
Monitor Ant., Montek	006300	N/A
Test Box - Interconnection - Montek	131500-703	N/A
Power Supply HP	6274B	1/16/78
Power Supply Acopian		12/9/77
Power Supply, Sorensen	QR4075A	9/19/77
Directional Coupler 20 dB, Narda	3042B	N/A
Directional Coupler 10 dB, Microlab	CBA-78	N/A
Variable Attenuator, Weinschel 0-10 dB	CBA-78	N/A
Variable Attenuator, Weinschel 0-10 dB	905	N/A
RF Attenuator, Weinschel	10 dB	N/A
Multimeter, Fluke	8120A	8/2/77
Aircraft, Beachcraft	Bonanza	N/A
Velocity, Multimeter, Datameter	800TP	12/12/77



**ATTACHMENT 2**

**DATA SHEETS**

**June 30, 1976**

June 30, 1976

## DATA SHEET

## OPERATIONAL TESTS

AN/TRN-41

Test WIND

System 003

Date 5/9/77

Time 2:00 PM

Tech

BEST AVAILABLE COPY

with 5/9/77  
with 5/9/77

Para. No.	Description	5/9/77 Pre Test m82	5/9/77 Post Test m82	Post Test	Requirements	Units
6.1	Calibrated RF insertion loss $P_L = 31.2 \text{ dB}$ Used in determining RF peak power.	N/A	N/A	N/A	N/A	N/A
6.2	System turn on normal operation	✓	✓		Check if OK	N/A
6.3.1	Antenna radiated signal 15 Hz	✓	✓		Check if OK	N/A
	135 Hz	✓	✓		Check if OK	N/A
6.3.2	Antenna Speed	66.667	66.668		66.667 ± .133	ms
6.4.1.1	Correct identity code	✓	✓		Check if OK	N/A
6.4.1.2	Identity period	38.0	38.0		37.5 ± 3.75	Seconds
6.4.2	Peak power (1) Reading of peak power meter $P_m =$ (2) Convert to dBm - 10 log $P_m \times 10^3 = P_m \text{ dBm}$ Total power output in dBm $P_{m \text{ dBm}} + P_L =$ *Insertion loss see 6.1 above.	76mw 18.81 dBm 50.01 dBm	76mw 18.81 dBm 50.01 dBm		N/A N/A 50 dBm	Watts dBm dB
6.4.3.3	Pulse count	7187	7184		7200 ± 180	Counts
6.4.4.2	Pulse shape Width (50%) Rise time (10-90%) Fall time (90-10%)	3.6µs 2.2µs 2.5µs	3.6µs 2.1µs 2.5µs		3.5 ± 0.5 2 ± 0.25 2.5 ± 0.5	µs µs µs
6.4.4.4	Pulse spacing	12.0µs	12.0µs		12.0 ± 0.1	µs
6.5.2	Delay - 60 ± 10 µs 15 Hz trig to first burst pulse.	✓	✓		Check if OK	

June 30, 1976

DATA SHEET  
OPERATIONAL TESTS  
AN/TRN-41 (Continued)

	Description	Pre Test	Test	Post Test	Requirements	Units
4.5.3	Correct north Burst - 12 pulse pairs spaced 30 ± 0.1 ps	✓	✓		Check if OK	
4.5.5	Delay 60 ± 10 ps - 135 Hz trig to first burst pulse	✓	✓		Check if OK	
4.5.6	Correct Aux burst - 6 pulse pairs spaced 24 ± 0.1 ps	✓	✓		Check if OK	
4.6.5	RT replies to 3000 interrogations	2508	2560		≥ 2310 (Counts/Second)	
4.6.7	Demand only mode - time to switch from ON to STBY within 70 seconds	✓	✓		Check if OK	✓
4.6.8	STBY mode	✓	✓		Check if OK	
4.6.9	Demand Only mode - time to switch from STBY to ON	✓	✓		Check if OK	
4.6.10	ON AIR mode	✓	✓		Check if OK	
4.7.1	DME ONLY mode	✓	✓		Check if OK	
4.7.2	Switch from DME to TACAN	✓	✓		Check if OK	
4.8.1	Antenna Alarm - Within four seconds	✓	✓		Check if OK	
4.8.2	Alarm Reset	✓	✓		Check if OK	
4.8.3	RT Alarm - Within five seconds	✓	✓		Check if OK	
4.8.4	Alarm Reset	✓	✓		Check if OK	

BEST AVAILABLE COPY

**THIS REPORT HAS BEEN DELIMITED  
AND CLEARED FOR PUBLIC RELEASE  
UNDER DOD DIRECTIVE 5200.20 AND  
NO RESTRICTIONS ARE IMPOSED UPON  
ITS USE AND DISCLOSURE.**

**DISTRIBUTION STATEMENT A**

**APPROVED FOR PUBLIC RELEASE,  
DISTRIBUTION UNLIMITED.**